

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN



1

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN



Introduction

- Client: OVAM (Flemish Waste Agency)
- 2 separate pilot projects in 2013
- Contractor: Jan De Nul – Envisan with 2 subcontractors for the heating techniques
- under supervision of OVAM, VITO and TEC
- Testing of several techniques on 1 of the most polluted sites in Flanders

2

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN

History

Fire in 1993

Chemical company Biochim totally destroyed
all of the stored **solvents** ended up in soil and groundwater

↓
LNAPL (pure product) spread over more than 1 ha




3

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN

Contaminants in soil vapour

- Cocktail of 132 measured, volatile and semi-volatile compounds
- Traces of PCB's and heavy metals
- PFOS is currently being investigated (no data known)



4

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN

Identified contaminants in LNAPL

- C9-C12 Aromatic Compounds
- C7-C40 Aliphatic Compounds
- Diethyl-Hexylphthalate
- Indane
- Di-isodecylphthalate isomers
- Biphenyl
- Biphenyl Oxide

PS: DNAPL will be investigated/remediated separately as part of a large scale remediation (multiple sources)

5

4 Pilots in 2011

- Soil vapour extraction + air treatment
- Multiphase-extraction (water / vapour / product) + treatment
- Confined space excavation
- LNAPL-recovery using different types of skimmers



➡ Conditions and limitations known



6


4 Pilots in 2011

- Soil Conditions:

Permeable sands (explosive vapours!) →

Loam with unconfined aquifer →

Permeable sands with confined aquifer →



- Contamination: highly toxic and explosive mixture

⇒ safety limitations for extraction, treatment and employees


7

THERMAL DESORPTION PILOT TESTING BIOCHIM MACHELEN

Thermally Enhanced Soil Vapour Extraction


1. Multiphase extraction + radio-frequency heating
2. Soil vapour extraction + hot air conduction

Goals:



8

1.1 MPE




Yellow: shallow sand SVE

Red: deep sand MPE

Green: loam MPE

9

1.1 MPE




Air extraction: $80 \text{ m}^3/\text{h}$ (DMVEX) + $260 \text{ m}^3/\text{h}$ (VAC) = $340 \text{ m}^3/\text{h}$

Air treatment: $500 \text{ m}^3/\text{h}$ (water treatment: $5 \text{ m}^3/\text{h}$)

10

1.1 MPE

%LEL
(undiluted)



Goal 1 achieved and area was far less contaminated than in 2011


252 kg mass removal in air phase during 3 months pilot (+ 4.63 kg water phase + LNAPL)

11

1.2 MPE + ISRFH


In-situ radio-frequency heating:

- waves in the MHz range cause an oscillating, electromagnetic field in the soil
- dielectric molecules rotate in this oscillating field
- the rotation causes friction which in turn heats the soil
- temperatures up to 300°C are theoretically possible




12

1.2 MPE + ISRFH



13


1.2 MPE + ISRFH



14

1.2 MPE + ISRFH

- only limited 'evidence' of increasing %LEL
(all other peaks due to shut-down and restart)



15

1.2 MPE + ISRFH

- Insufficient heating: 25°C on average at 3 mbgl
- A lot of problems due to:
 - Fluctuating groundwater level
 - Electrodes at water interface, impedance correction for both unsaturated and saturated area was required
 - Coax cable got damaged (corrosion + arcing)
 - Matchbox got seriously damaged (overheated due to impedance problem)
- 28.143 kWh used for the heating over 49 days
- 54.687 kWh + 3,959.4 L propane used for extraction and treatment (4.5 months)
- Conclusions:
 - not suited for loamy layer with water interface
 - 2 matchboxes required (saturated and unsaturated areas separated)

16


2. SVE and conductive heating

- hot air conduction : a strong temperature gradient is installed in the soil by using a tight network of closed pipes, transporting burning gases
- the hot air in het pipes has a temperature above 250°C
- transfer of heat by conduction



17

2. SVE and conductive heating



18



2. SVE and conductive heating

- SVE : 150 m³/h and treatment of 500 m³/h (catox + scrubber)
- 350 m³/h fresh air dilution as a function of measured LEL !!



19

2. SVE and conductive heating




- 25,716 L of Propane used
- 5,498 kWh used for burners
- August 30 – November 6

Heating achieved

20

2. SVE and conductive heating



Goal 2 achieved and area was far more contaminated than the ISRFH area

877.5 g/u mass removal without heating and 966.4 g/u with heating but with higher dilution and hence lower extraction rate

21

2. SVE and conductive heating

- Smear zone heating until 6 mbgl was required: heating tubes were put in permeable sands
- Very efficient heating
- Extraction had to deal with vaporized LNAPL and steam, resulting in 100% LEL



- High vapour pressure in the soil

22

2. SVE and conductive heating

- tubes = iron = expansion during heating
- very hard to seal -> vapours escaping
- ambient air monitoring
- biomonitoring
- eventually shut down due to neighbouring houses
- proposal for limited heating area was not accepted
- proposal for C3 treatment (cooling, compression and condensation) was not accepted
- proposal for ERH was not accepted



23

CONCLUSIONS

- thermal desorption works
- MPE works
- MPE and/or SVE is required prior to heating in order to lower contaminant release (zone MPE versus zone SVE)
- heating should be saved for local hot spots
- heating either too slow or too fast
- hard to heat both saturated and unsaturated zone
- ERH (6- or 3-phase) is an alternative but humidification of the unsaturated zone is then required

24

Questions?